HELL IN HIGH WATER
Shop Order

UMASS
Department of Theater

Lighting Designer: Jessica Greenberg
Cell: 518-522-1683
jess@jessicagreenberg.com
greenberg.jessica@gmail.com
www.jessicagreenberg.com

Master Electrician: Brittany Deventer
bdevente@student.umass.edu
Cell: 973-598-5556

Shop Order Created: October 12, 2011
REVISED: October 16, 2011 by JMG

General Notes:

• Entire lighting package is to be made ready by the Lighting Shop and is to include all connectors, cables, controls, frames, and other necessary equipment to comprise a complete working system.

• All units are to come with a lamp (wattages noted), c-clamp, and safety cable unless otherwise specified in writing.

• Absolutely no substitutions with the written permission of the Lighting Designer.

• Any revisions or substitutions must be fully disclosed before the load-in date.

• All perishables per Master Electrician.

Equipment Summary:

Qty	Instrument Type	Watt		
8	1 Cell Sky Cyc	1kw	8	Total
10	3 Cir EconoCyc Ground	500w	11	Total
7	3 Cell Sky Cyc	1kw	7	Total
4	3 Cir 6'4" ZipStrip	750w	4	Total
2	5000S Studio 12" Fresnel	5kw	2	Total
14	ALT 6x12	750w	14	Total
12	ALT 6x16	750w	12	Total
3	MINI 10	150w	3	Total
12	PAR 64 MFL	1kw	12	Total
6	PAR 64 NSP	1kw	6	Total
6	PAR 64 VNSP	1kw	6	Total
3	STROBE	100w	3	Total
5	R40 3 Cir 6' Strip	1.2kw	5	Total
12	S4 PAR MFL	575w	12	Total
8	S4 PAR NSP	575w	8	Total
5	S4-10°	575w	5	Total
71	S4-19°	575w		
2	S4-19°	750w	73	Total
55	S4-26°	575w	55	Total
40	S4-36°	575w		
17	S4-36°	750w	57	Total
2	S4-50°	575w		
2	S4-50°	750w	4	Total

TOTAL LIGHTS: 306

Accessory Summary:

ACCESSORY COUNT

6.25" Bway Scroll
6 for S4-36°
---
6 Total

7.5" ChromaQ Scroll
20 for S4 PAR
---
20 Total

DMX Iris
2 for S4-19°
---
2 Total

I-Cues
2 for S4-19°
---
2 Total

Gobo Rotators
5 for S4
---
5 Total

Film FX
4 for S4
---
4 Total

A-Template Holder
17 for S4
---
17 Total

6.25” Top Hats
62 for S4
---
62 Total

1 Hazer
1 Fogger

COLOR COUNT

Color Cuts

L201

R40 3 Cir 6' Strip	5 cuts
Total:	5 cuts

L203

S4-26°	4 cuts
Total:	4 cuts

R09

S4-19°	10 cuts
Total:	10 cuts

R104

3 Cir 6'4" ZipStrip	12 cuts
3 Cell Sky Cyc Right	7 cuts
3 Cell Sky Cyc Left	7 cuts
3 Cell Sky Cyc Center	7 cuts
1 Lt EconoCyc Ground	30 cuts
R40 3 Cir 6' Strip	15 cuts
Total:	78 cuts

R119

S4-26°	42 cuts
S4-19°	63 cuts
S4-10°	5 cuts
S4-36°	13 cuts
ALT 6x12	14 cuts
ALT 6x16	12 cuts
Total:	149 cuts

R132

S4-26°	3 cuts
S4-19°	3 cuts
S4-36°	37 cuts
S4-50°	2 cuts
Total:	45 cuts

R304

S4-26°	7 cuts
S4-36°	2 cuts
3 Cir 6'4" ZipStrip	4 cuts
5000S Studio 12" Fresnel	1 cut
Total:	14 cuts

R316

PAR 64 MFL	6 cuts
PAR 64 NSP	3 cuts
Total:	9 cuts

R317

1 Lt EconoCyc Ground	10 cuts
Total:	10 cuts

R3202

S4-36°	5 cuts
S4-50°	2 cuts
3 Cir 6'4" ZipStrip	4 cuts
ALT 6x16	6 cuts
Total:	17 cuts

R3204

PAR 64 MFL	6 cuts
PAR 64 NSP	3 cuts
Total:	9 cuts

R3206

S4-26°	16 cuts
S4-19°	38 cuts
S4-10°	5 cuts
S4-36°	13 cuts
Total:	72 cuts

R3208

S4-26°	5 cuts
S4-19°	8 cuts
S4-36°	17 cuts

S4-50° 2 cuts
ALT 6x12 14 cuts

Total: 46 cuts

R3220
S4-26° 6 cuts
S4-36° 6 cuts
5000S Studio 12" Fresnel 1 cut
1 Lt EconoCyc Ground 10 cuts

Total: 23 cuts

R325
3 Cell Sky Cyc Left 7 cuts

Total: 7 cuts

R359
3 Cell Sky Cyc Center 7 cuts

Total: 7 cuts

R375
S4-36° 4 cuts

Total: 4 cuts

R38
ALT 6x16 6 cuts

Total: 6 cuts

R384
3 Cir 6'4" ZipStrip 4 cuts
3 Cell Sky Cyc Right 7 cuts
R40 3 Cir 6' Strip 5 cuts

Total: 16 cuts

R42
R40 3 Cir 6' Strip 5 cuts

Total: 5 cuts

R55
S4-26° 6 cuts

Total: 6 cuts

R57
S4-26° 7 cuts

Total: 7 cuts

R68
S4-19° 10 cuts
S4-36° 4 cuts

Total: 14 cuts

R83
S4-19° 7 cuts
1 Lt EconoCyc Ground 10 cuts

Total: 17 cuts

SCROLL 2
S4 PAR MFL 12 scrolls
S4 PAR NSP 8 scrolls

Total: 20 scrolls

Broadway Scroll
S4-36° 6 scrolls

Total: 6 scrolls

<u>GOBO COUNT</u>

G643 Moonscape
7 for S4-19°
.....
7 Total

R33621 Glass Dune
2 for S4-36°
.....
2 Total

R77807 Dot Breakup
1 for S4-36°
2 for S4-50°
.....
3 Total

TBA STOCK WINDOW
2 for S4-26°

TBA STOCK Breakup
4 for S4-36°

INSTRUMENT COUNT by POSITION

FOH 4
(All instruments on 3' sidearm)

Qty	Instrument Type	Watt		
1	S4-10°	575w	1	Total
1	S4-19°	575w	1	Total

1 S4 A-Template Holder

FOH 3

Qty	Instrument Type	Watt		
2	S4-10°	575w	2	Total
11	S4-19°	575w		
1	S4-19°	750w	12	Total

3 S4 A-Template Holder
1 I-CUE
1 DMX IRIS

FOH 2

Qty	Instrument Type	Watt

2	S4-10°	575w	2	Total
10	S4-19°	575w	10	Total
3	S4-26°	575w	3	Total

3 S4 A-Template Holder

FOH 1A

Qty	Instrument Type	Watt		
6	PAR 64 NSP	1kw	6	Total
6	S4-19°	575w	6	Total
1	S4-36°	750w	1	Total
1	Gobo Rotator			

1E TRUSS DS

Qty	Instrument Type	Watt		
6	PAR 64 MFL	1kw	6	Total
6	S4-19°	575w	6	Total
4	S4-26°	575w	4	Total
2	S4-50°	575w	2	Total

1E TRUSS US

Qty	Instrument Type	Watt		
3	ALT 6x12	750w	3	Total
1	STROBE	100w	1	Total
1	S4-19°	575w	1	Total

2	S4-26°	575w	2	Total
4	S4-36°	575w	4	Total
1	S4-50°	750w	1	Total
2	Gobo Rotator			

2E

Qty	Instrument Type	Watt		
6	PAR 64 MFL	1kw	6	Total
2	STROBE	100w	2	Total
6	S4-19°	575w		
1	S4-19°	750w	7	Total
4	S4-26°	575w	4	Total
1	S4-36°	575w	1	Total
1	S4-50°	750w	1	Total
3	Gobo Rotator			

1 DMX Iris
1 I-CUE

3E

Qty	Instrument Type	Watt		
2	5000S Studio 12" Fresnel	5kw	2	Total
5	ALT 6x12	750w	5	Total
6	PAR 64 VNSP	1kw	6	Total
6	S4 PAR MFL	575w	6	Total

4	S4 PAR NSP	575w	4	Total

2	S4-26°	575w	2	Total

6	S4-36°	575w	6	Total

2 S4 A-Template Holder

7.5" ChromaQ Scroll
6 for S4 PAR MFL
4 for S4 PAR NSP

10 Total

4E

Qty	Instrument Type	Watt		
5	ALT 6x12	750w	5	Total
6	S4 PAR MFL	575w	6	Total
4	S4 PAR NSP	575w	4	Total
2	S4-26°	575w	2	Total
3	S4-36°	575w	3	Total

2 S4 A-Template Holder

7.5" ChromaQ Scroll
6 for S4 PAR MFL
4 for S4 PAR NSP

10 Total

5E

Qty	Instrument Type	Watt		
4	3 Cir 6'4" ZipStrip	750w	4	Total
2	S4-36°	575w		
4	S4-36°	750w	6	Total

4 Gobo Rotator

.....

4 S4 A-Template Holder

6E

Qty	Instrument Type	Watt		
5	R40 3 Cir 6' Strip	1.2kw	5	Total
4	S4-36°	750w	4	Total

7E

Qty	Instrument Type	Watt		
7	3 Cell Sky Cyc Center	1kw	7	Total
7	3 Cell Sky Cyc Left	1kw	7	Total
7	3 Cell Sky Cyc Right	1kw	7	Total

1E LADDER L

Qty	Instrument Type	Watt		
2	S4-26°	575w	2	Total
1	S4-36°	575w	1	Total

2E LADDER L

Qty	Instrument Type	Watt		
2	S4-26°	575w	2	Total
1	S4-36°	575w	1	Total

1E LADDER R

Qty	Instrument Type	Watt

2	S4-26°	575w	2	Total
1	S4-36°	575w	1	Total

2E LADDER R

Qty	Instrument Type	Watt		
2	S4-26°	575w	2	Total
1	S4-36°	575w	1	Total

1 BOOM L

Qty	Instrument Type	Watt		
3	S4-26°	575w	3	Total

2 BOOM L

Qty	Instrument Type	Watt		
2	S4-26°	575w	2	Total
2	S4-36°	575w	2	Total
2	Film/FX	100w	2	Total

3 BOOM L

Qty	Instrument Type	Watt		
5	S4-36°	575w	5	Total

4 BOOM L

Qty	Instrument Type	Watt		
2	S4-36°	575w		
3	S4-36°	750w	5	Total

.....
6.25" Bway Scroll
3 for S4-36°
---
3 Total

1 BOOM R

Qty	Instrument Type	Watt		
3	S4-26°	575w	3	Total

2 BOOM R

Qty	Instrument Type	Watt		
2	S4-26°	575w	2	Total
2	S4-36°	575w	2	Total
2	Film/FX	100w	2	Total

3 BOOM R

Qty	Instrument Type	Watt		
5	S4-36°	575w	5	Total

4 BOOM R

Qty	Instrument Type	Watt		
2	S4-36°	575w		
3	S4-36°	750w	5	Total

.....
6.25" Bway Scroll
3 for S4-36°
---
3 Total

COVE L

Qty	Instrument Type	Watt		
2	S4-19°	575w	2	Total
3	S4-26°	575w	3	Total
1	S4-36°	575w	1	Total

BBL 1

Qty	Instrument Type	Watt		
6	ALT 6x16	750w	6	Total
3	S4-19°	575w	3	Total
7	S4-26°	575w	7	Total

BBL 2

Qty	Instrument Type	Watt		
10	S4-19°	575w	10	Total

COVE R

Qty	Instrument Type	Watt		
2	S4-19°	575w	2	Total
3	S4-26°	575w	3	Total
1	S4-36°	575w	1	Total

BBR 1

Qty	Instrument Type	Watt		
6	ALT 6x16	750w	6	Total
3	S4-19°	575w	3	Total

7	S4-26°	575w	7	Total

BBR 2

Qty	Instrument Type	Watt		
10	S4-19°	575w	10	Total

FLOOR

Qty	Instrument Type	Watt		
1	FOGGER		1	Total
1	HAZER		1	Total

FLOOR MOUNT

Qty	Instrument Type	Watt		
2	MINI 10	150w	2	Total
2	S4-36°	750w	2	Total

PROSC MOUNT

Qty	Instrument Type	Watt		
1	ALT 6x12	750w	1	Total

G/ROW

Qty	Instrument Type	Watt		
8	1 Cell Sky Cyc	1kw	8	Total
10	1 Lt EconoCyc Ground	500w	10	Total

--- End of Report -----