

2010

## Erosion and Sediment Control

Hilary A. Sandler

*University of Massachusetts - Amherst*, [hsandler@umass.edu](mailto:hsandler@umass.edu)

Carolyn J. DeMoranville

*University of Massachusetts - Amherst*, [carolynd@umext.umass.edu](mailto:carolynd@umext.umass.edu)

Larry Boutiette

NRCS

Follow this and additional works at: <https://scholarworks.umass.edu/cranberrybmp2010>

---

Sandler, Hilary A.; DeMoranville, Carolyn J.; and Boutiette, Larry, "Erosion and Sediment Control" (2010). *Cranberry Station Best Management Practices Guide - 2010 revision*. 12.

Retrieved from <https://scholarworks.umass.edu/cranberrybmp2010/12>

This Article is brought to you for free and open access by the Cranberry Station Outreach and Public Service Activities at ScholarWorks@UMass Amherst. It has been accepted for inclusion in Cranberry Station Best Management Practices Guide - 2010 revision by an authorized administrator of ScholarWorks@UMass Amherst. For more information, please contact [scholarworks@library.umass.edu](mailto:scholarworks@library.umass.edu).

## ***Erosion and Sediment Control***

Erosion and sedimentation pose problems for soil conservation and water quality maintenance. Erosion control is an important component of non-point pollution prevention programs since soil itself can be both a contaminant and a carrier of other pollutants such as pesticides and nutrients. Under the Massachusetts Wetlands Protection Act, erosion and sediment must be kept to a minimum in order for practices to continue to qualify as Normal Maintenance or Improvement of Land in Agricultural Use. Since cranberries are grown in proximity to sensitive water bodies and wetlands, it is essential that growers use the best practices available to control erosion.

Most cranberry agricultural activities do not give rise to significant levels of off-site erosion. In fact, many of the strategies recommended for reducing erosion and sedimentation are normal farming practices of the cranberry industry. Bogs are typically constructed on nearly level to slightly depressed landscapes, so runoff and erosion are minimized. Secondly, strict control of water flow through the bogs is critical to successful growing and harvesting of cranberries. Water control structures function to control water volume and velocity. Therefore, waterways in cranberry bogs tend to be less subjected to storm-related erosion events. Also, cranberry water systems often include water storage ponds that act as settling ponds that further reduce off-site sediment discharge. Finally, cranberry growing conforms to conservation farming principles in that the soil is not disturbed once the crop is established.

Sources of water and wind eroded sediments associated with cranberry production are generally related to atypical or occasional activities, such as land clearing, new bog construction or renovation, operations associated with sanding (namely excavating and stockpiling of sand resources and sand application), and ditch cleaning and maintenance. In some bogs, especially those with perennial streams flowing through them, stream or ditch bank erosion can pose a concern. This BMP is designed to point out ways to minimize erosion and sediment during these activities.

Information is also provided regarding the construction and maintenance of sediment barriers.

*Make sure that you are familiar with and in compliance with State and Federal Wetlands Protection regulations.*

For more information on E&S Best Management Practices, you can reference the Massachusetts DEP document, "Massachusetts Erosion and Sediment Control Guidelines for Urban and Suburban Areas: a guide for planners, designers and municipal officials". This document is also available on-line at: <http://www.mass.gov/dep/water/essec1.pdf>.

## **Recommended Practices**

### **Erosion and sediment prevention methods-New construction and bog renovation**

Disturbing large areas of land carries with it the risk of erosion. Soil erosion can damage water bodies and aquatic life. Small plants and invertebrate animals can be smothered by silt that may also damage the gills of fish. Sediments may also serve to carry pollutants into water. For example, phosphorus is often bound to soil particles at low pH and may be carried with sediment, stimulating algal growth in receiving water bodies. Proper planning for the control of

erosion prior to the start of any construction or earthmoving activities will ensure that wetlands and water bodies are protected and that you remain in compliance with the Massachusetts Wetland Protection Act. The Act **requires** that erosion and sediment be minimized as part of the Normal Maintenance or Improvement of Land in Agricultural Use practices.

It is important to formulate an erosion control plan **prior** to the start of any construction activity. The erosion control plan, including planning for where runoff water will go during construction, should be part of your overall project plan. Materials needed for implementing that plan should be on hand or installed prior to earth disturbance. It is vital to have erosion control measures in place prior to substantial rainfalls or storms.

For most effective erosion control:

- Formulate a plan for erosion control.
- Minimize and stabilize disturbed areas.
- Protect disturbed areas from runoff and minimize runoff velocity.
  - Prevent sediment from moving off of your site.
- Regularly inspect and maintain erosion and sediment control structures and materials.

**Pre-construction planning**

Plan for water movement on your site. If possible, plan to divert water around the site. Soil laden runoff should be kept out of sensitive water bodies. It may be necessary to plan for retention ponds to hold such runoff for sedimentation prior to release. All such plans should be based on handling a large rain event, e.g. 4+ inches in 24 hours.

Plan dikes with side slopes no greater than 1:1. While steeper slopes allow for a larger planting area, they are more vulnerable to erosion. Steep dikes will continue to be more difficult to maintain for the life of the planting.

Plan to install silt fencing and barriers.

Have all required erosion control materials on site.

**Erosion control during construction**

Before starting a project, develop a plan to control construction related impacts (e.g., erosion, sedimentation) during construction and land disturbance activities. Construct water management and control features first. Recovery ponds constructed now can act as silt basins. The captured material may be useful later in dike construction. Divert channeling water around the disturbed area, as common silt barriers are only effective against sheeting runoff across the site.

**Install silt fencing and barriers.**

Silt fencing should be installed along the down slope property edge. It must be in place before any soil is disturbed. Instructions for constructing silt barriers are found in the last section of this BMP. Silt fences must be inspected after every rainfall and properly maintained to minimize soil movement. These barriers protect water bodies as well as neighbors properties and public ways.

**Disturb as little of the site as possible.**

When constructing multiple beds, open up the site progressively. Stabilize the site as you go along. Leave existing vegetation in place elsewhere on the site as much as possible. If you have problems with dust and wind erosion, control by sprinkling water on dry soil or sand. Keep your site neat. This will help to control erosion and will also be looked upon favorably by your neighbors.

**Maintain soil and sand stockpiles properly.**

Excavated sand should be stockpiled as far away as possible from water bodies and drainage ways. Soil stockpiles can be stabilized by seeding or mulching. This should be done if stockpiles will remain for more than a week or two. Down gradient silt barriers may also be needed. The potential impact on neighbors should be determined when establishing height and location of stockpiles.

**Avoid loss of soil from roadways during construction.**

Dust on roadways can be controlled by sprinkling water. Grass or vegetation should be established on roadways, dike roads, etc. as soon as possible. Placement of coarse gravel in the site roadways at the exits will prevent tracking of soil onto public roadways. For this practice, coarse gravel (2-3 inches) is placed 6 inches deep by 7 feet wide for the final 50 feet of the exit roadway.

Avoid disturbing soil during adverse weather conditions.

**Work during dry seasons.**

Do not work on the site when the soil is frozen or saturated or during heavy rain or wind storms. When large rain events are predicted, putting a shallow flood over the bed can be protective against erosion losses.

### **Dike construction and stabilization**

**Construction.**

Embankments should be built no steeper than 1:1. Site the shallower slope on the outside of the dike to minimize off-site erosion. The dike should be built and compacted in layers using fill materials containing no sod, brush, roots, stumps, or rocks larger than 6 inches. Core materials in the dike should be the most impervious materials available. In Southeastern Massachusetts, this will often be compacted glacial till. Dikes should be constructed to a height 1 foot above the normal flood elevation. In order to establish vegetation on dikes or embankments, surface soil must have the capacity to hold adequate water to support plant growth (see NRCS standard for cranberry bog dike construction, <http://efotg.nrcs.usda.gov/references/public/MA/356.pdf>).

**Stabilization.**

Stabilize dikes and other disturbed areas by seeding to grass or other types of vegetation stabilization plants, by mulching, or by placing soil stabilization fabric (geotextile, netting, or burlap). Mulch should be anchored with a biodegradable netting. Grade 2-3 turf sods have been used successfully for this purpose. Pay particular attention to dike edges, they remain prone to erosion during rainstorms until stabilized. Keep woody plants off of dikes as their roots can destabilize the structure. Avoid ponding (wheel tracks) on top of dikes.

Erosion control blankets (e.g., Curlex), have been successfully used to stabilize bankings and on-bed ditch edges. Ditches stabilized with these products required 60% less cleaning than those left untreated. Erosion blankets are preferable to loose mulch on the bog side of a dike,

as mulch may contain weed seeds that will end up in the bed. Erosion control blankets are biodegradable, decomposing in 6-8 months. The material must be in good contact with the underlying soil or erosion can occur under the blanket.

Grass is best planted in spring or fall and may benefit from a layer of mulch or netting and periodic watering during establishment. Top dress dikes with 3-4 inches of topsoil prior to seeding. Hydroseeding or gel seeding can be used. Erosion control blankets have been successful in conjunction with grass planting. Studies have shown that germination rate rose from 50-60% to 85-95% when blankets were used over grass seed. Pre-seeded blankets are available.

Choose non-weedy species for seeding dikes. Recommended examples include clovers, fescues, and perennial ryegrass. Mixtures of species in the seed mix are preferable to a single species. Fertilize and lime grasses as needed during establishment. See the reference "Is it time to rethink grass slopes?" at the end of the section.

### **Flume installation, protection, and stabilization**

#### **Installation.**

Flumes should be fitted with antiseep collars and constructed into native soil if possible. Fill and compact around the culvert to prevent piping (formation of eroded channels). Packing with bentonite or other dense materials may be helpful.

Placement of concrete blocks around the flume may also help.

The size of the outlet pipe is important. If it is too small, the culvert may wash out. Size is determined based on the amount of water required for flooding, de-flooding, and handling of a chosen storm event. Consult an engineer or NRCS for this calculation.

Water should be discharged into a stable ditch or channel.

#### **Protection and stabilization.**

Use a riprap apron with underlying geotextile at the entrance and exits of outlet flumes where the velocity of flow could cause erosion. The geotextile protects the riprap from undercutting and can be placed directly on leveled soil. A gravel base may be substituted for the fabric. The riprap apron is necessary if capacity flow from the outlet results in the formation of plunge pools. These can severely weaken embankments and threaten stability. The riprap apron also prevents scouring at the culvert mouth and prevents gully erosion that could gradually extend upstream.

The riprap structure should be installed early in construction but can be added later. Once installed they should be inspected regularly for any movement or displacement of the rock. Removal of sediment buildup may be difficult and generally requires hand labor.

### **Erosion and sediment prevention methods - all beds**

#### **Controlling stream bank and ditch bank erosion.**

A common result of this type of erosion in cranberry systems is the loss of functionality of ditches and canals. Ditches lose drainage capacity due to sedimentation and canals can lose capacity due to bank slumping.

**Manage water to minimize erosion, slumping, and undercutting of bankings.**

Stream or ditch bank erosion commonly occurs when saturated, unstable soil materials are subject to high volume and velocity water flow followed by rapid drawdown (common in sandy soils). Reduce the erosive potential of moving water by slowing the flow velocity at the flume.

Lower water levels in ditches to improve slope and bank stability during times of the season when soil is wet. This is especially common in the spring during periods of rain and/or sprinkling for frost. Water levels in ditches should be higher in times of drought. Saturated soil has very little strength; lowering water levels in ditches dries out the soil and reduces slump and failure of sidewalls.

**Use vegetation or other materials to stabilize bankings.**

Establish a good stand of grass on dikes. This will stabilize the soil and prevent waterlogging (vegetation facilitates water loss by transpiration).

Try to establish cranberry vines or other vegetation on the sidewalls of ditches. The roots will anchor the soil, increase soil stability, and reduce slumping. Erosion blankets such as Curlex may be used to aid in establishment of vegetation on bankings and in holding the bed edges in place until the cranberry plants are well established.

Apply geofabric or geogrid materials to unstable embankments to increase shear strength and reduce slumping.

**Install protective features.**

Install energy dispersing or deflecting barriers (e.g., rocks, riprap) wherever discharging water flows in direct contact with a ditch sidewall. This will occur where discharging internal flumes are set at right angles to the shore ditch or canal and large volumes of water are being released, e.g. harvest flood.

Add rip rap stone to the down gradient side of flumes to prevent stream or ditch bed scouring. Large irregular stones placed in the stream or ditch bed dissipate the energy of high velocity water exiting the bog. The loss of energy by the water significantly reduces scouring and sediment transport. This practice is regulated under the Massachusetts Wetlands Protection Act - make sure you are in compliance when using rip rap stone.

## Sanding

**Stockpile sand responsibly.**

The stockpiling of sand should be limited as much as possible. Loss to water and wind erosion is inevitable if sand piles are left in place for long periods of time.

Excavated sand should be stockpiled as far away as possible from water bodies and drainage ways. Down gradient silt barriers may also be needed. All efforts should be made to minimize wind erosion.

Consider the impact on neighbors when establishing height and location of stockpiles.

**Avoid discharge of sand laden waters.**

This is critical when barge sanding. Retain flood water for an adequate period to allow settling, usually 5-7 days or longer.

Sand laden water may also be generated following other sanding methods if sand is 'watered-

in' by hosing or shallow flooding. Precautions after such practices should be similar to those used when barge sanding.

Follow practices recommended in the Sanding BMP.

### **Ditch cleaning**

Take precautions to preserve the integrity of stream and ditch bankings. Be careful not to undercut stream or ditch banks or to dig ditches too deeply during ditch cleaning. Undercutting leads to instability and bank failure.

Avoid discharge of sediments during ditch cleaning.

If fine textured sediment is being dredged from ditch bottoms, consider using a silt fence to trap sediments before they move offsite.

Cleaning ditches from the point most distant from the flume (moving towards the flume) will enhance settling of sediments.

Allow dredged sediments ample time to drain of excess water before being moved significant distances. Use a sediment barrier as necessary to keep the sediments contained.

### **Construction and maintenance of sediment barriers**

#### **General**

Growers should employ all reasonable sediment capture and removal techniques to receive and cleanse waters exiting the bog. Growers should also consider diverting sediment charged water to holding ponds to allow settling of solids. Filter strips or filter booms with hanging cloth may also be effective.

Sediment barriers are necessary if drainage across a disturbed area could deposit sediment into a water body, a wetland, or a neighbor's property. They are not needed if the site drains into a tailwater recovery pond or the bog itself.

Note: Most sediment barriers are designed to handle sheet erosion only.

All sediment barriers should be inspected immediately after any rainfall, at least daily during rainy periods, and if there is any sign of downstream erosion.

Sediment must be removed from behind the barrier if it reaches  $\frac{1}{2}$  the height of the barrier. If there are signs (small and localized) of undercutting or impounding of large volumes of water behind a sediment barrier, a second barrier should be installed. If the undercutting or water impoundment is more extensive or is occurring from flow greater than sheet flow or the contributing drainage area is too large, then switching to a more suitable BMP might be a better choice.

If the barrier shows signs of decomposition or clogging, it should be replaced promptly.

Once the barriers are no longer needed, they should be removed and the remaining sediment should be graded and seeded.

Do not install bales or fencing across streams, ditches, or waterways.

### **Straw or hay bales**

This is a temporary and inexpensive sediment barrier consisting of a row of entrenched and anchored straw/hay bales. This structure will intercept and detain small amounts of sediment from disturbed areas and will prevent offsite movement to a limited extent. The velocity of sheet flows will also be decreased.

Contributing drainage area should be less than one acre. These structures are effective for no more than 3 months.

### **Planning and installation.**

Locate the barrier where there will be sediment laden runoff — near the base of the drainage area. Ideally there will be an undisturbed, vegetated area further downslope of the barrier.

Dig a trench at least 4 inches deep, removing all grass. Flare ends uphill to increase storage capacity.

Place wire-bound or string-tied bales tightly, end to end, in the trench.

Anchor each bale with at least 2 stakes or re-bars driven through the bale. Angle stakes to force bales together.

Fill gaps by carefully wedging loose straw between bales.

Backfill excavated soil against the barrier. Fill to ground level on downslope side and build up 4 inches on upslope side.

Loose straw scattered on upslope side will increase effectiveness of barrier.

### **Potential problems with bales.**

These barriers are not effective in areas with high water velocities or volumes.

If improperly constructed, water flow will undercut the barrier and actually increase erosion.

These barriers are effective for approximately three months; less if improperly maintained.

### **Maintenance of bales.**

Inspect after each runoff-producing rainfall and daily during prolonged rainy periods. Check for flow around ends of barrier. Repair damaged bales and under cut areas promptly.

Remove sediment deposits when they reach 1/2 of the height of the barrier.

When the barrier is no longer effective or the project is finished, remove the barrier and dispose of it properly. The remaining sediments should be leveled and vegetated.

### **Sediment fencing**

This is a temporary sediment barrier consisting of filter fabric stretched across and attached to supporting posts and entrenched. Additional, rigid wire fencing may be needed in some areas of the barrier as support. This structure will intercept and detain small amounts of sediment from disturbed areas during construction and reduces runoff velocity down a slope. As with



the bale barriers, these structures are designed for sheet runoff only (no channeling). Sediment fences may also be used to catch wind-blown sand.

Contributing drainage area should be less than 1/4 acre per 100 feet of fence; and no more than 1.5 total acres. These structures are effective for approximately 6 months. In addition to their longer effective life, sediment fences trap a much higher percentage of sediments than do straw bales. Currently, it is common to use both and this approach is endorsed by MassDEP.



Compost blanket



Geotextile mats

### **Planning and installation.**

Locate the barrier where there will be sediment laden runoff -- but at least 10 feet past the base of the slope in the drainage area to provide sediment storage and access for cleanout. Access must be provided to locations where sediment accumulates and reinforced, stabilized outlets must be in place for emergency overflow. Do not locate where ponding behind the fence will cause property damage or create a safety hazard. The fenceline should be nearly level along its length, but should swing slightly uphill for the last 10-20 feet at each end (approx. 6 inch elevation) to provide storage capacity.

Dig a trench 8 inches deep and 4 inches wide or a V-trench.

Drive support posts in at least 16 inches, on the downslope side of the trench. Use 4 inch diameter pine, 1.33 lb./linear ft. steel, or 3 inch diameter quality hardwood posts. Steel posts should have projections for fastening fabric. Posts should be placed no more than 6 feet apart; 8 feet if support wire is to be used.

Fasten support wire to upslope side of posts. Wire should extend 6 inches into the trench. Use 14 gauge wire with 6-inch mesh.

Attach continuous length of filter fabric to upslope side of supports. Avoid joints, especially at the low point of the fence.

Extend fabric one foot into trench and backfill with compacted earth or gravel.

If large amounts of sediment are expected, a shallow storage area may be excavated upslope of the fence.

Provide for safe bypass of storm flow. Set stabilized, reinforced outlet so that no more than 1.5 feet of water is held behind the fence at the lowest point. Set the outlet within the fence with posts no more than 4 feet apart and fabric no more than 1 foot above surface. Install a horizontal brace to hold the fabric. Provide a riprap splash pad 5 feet by 5 feet by 1 foot deep on level grade on the downslope side of the outlet in the fence.

#### **Potential problems with sediment fencing.**

These barriers are not effective in areas with high water velocities or volumes and will not control runoff for anything deeper than sheet flow.

If improperly constructed, water flow will undercut the barrier and actually increase erosion. The bottom of the fence should be buried at least 8 inches deep and the trench should be backfilled with compacted earth or gravel.

#### **Maintenance of sediment fencing.**

Inspect after each runoff-producing rainfall and daily during prolonged rainy periods. Check for flow around ends of barrier. Repair as necessary.

Remove sediment deposits to provide adequate storage and remove pressure on the fence but take care not to undermine the fence when removing sediment.

If the fabric tears or decomposes, replace it immediately.

When the barrier is no longer effective or the project is finished, remove the barrier and dispose of it properly. The remaining sediments should be leveled and vegetated.

#### **Source materials:**

NRCS Fact Sheets.

**Straw / hay bale barriers:**

<ftp://ftp-fc.sc.egov.usda.gov/WSI/UrbanBMPs/water/construction/strawbale.pdf>.

**Sediment (silt) fences:** <http://www.wy.nrcs.usda.gov/technical/ewpfactsheets/siltfence.html>.

**Geotextiles:** <http://www.cabmphandbooks.org/Documents/Construction/EC-7.pdf>.

**Rock outlet protection and stabilization.**

<http://www.wy.nrcs.usda.gov/technical/ewpfactsheets/rockoutlet.html>.

**Cranberry beds construction planning guide: Erosion control for cranberry bed development.** Maine DEP in cooperation with the Cranberry Technical Workgroup.  
<http://extension.umaine.edu/cranberries/growing-cranberries/erosion-control-guidelines/>.

**For more information:**

**Dike standard.** 1980. Natural Resources Conservation Service Practice Standard #356. NRCS-NHCP. Amherst, MA. <http://efotg.nrcs.usda.gov/references/public/MA/356.pdf>.

Howland, M.A. 1998. **Is it time to rethink grass slopes?** *Cranberries* 62(7): 16-17.

Howland, M.A. 1997. **Building with erosion blankets from slope to bed.** *Cranberries* 61(9): 14-15.

Massachusetts Erosion and Sediment Control Guidelines for Urban and Suburban Areas: a guide for planners, designers and municipal officials". This document is also available on-line at: <http://www.mass.gov/dep/water/essec1.pdf>.

Planer, T.D. 1993. **Recommended procedures for using turf to stabilize roadways, dikes and ditchbanks.** Proceedings 1993 Wisconsin Cranberry School. pp. 31-33.  
<http://www.library.wisc.edu/guides/agnic/cranberry/proceedings/1993/recpla.pdf>.

*Updated by Hilary Sandler, Carolyn DeMoranville, and Larry Boutiette (senior engineer, NRCS). 2010.*

## ***Erosion and Sediment Control Checklist***

- ✓ Make sure you are familiar with and in compliance with State and Federal Wetlands Protection regulations.
- ✓ The MA Wetlands Protection Act (WPA) requires that erosion and sediment be minimized as part of the Normal Maintenance or Improvement of Land in Agricultural Use practices.
- ✓ Formulate an erosion control plan prior to the start of any construction activity.
- ✓ Protect disturbed areas from runoff and minimize runoff velocity.
- ✓ Regularly inspect and maintain erosion and sediment control structures and materials.
- ✓ Understand the limitations associated with the various sediment barriers.
- ✓ Periodically check the elevation of the earthfills and restore to grade, if necessary.
- ✓ Check all areas where embankment protection was installed (rock riprap, woods turf, sod, etc.) for accelerated weathering or displacement repair or replace as needed.